CITY OF COSTA MESA
DEPARTMENT OF PUBLIC SERVICES

2004-2005 SLURRY SEAL AND CRACK SEAL PROJECT

PROJECT NO. 05-11

BID OPENING DATE: JUNE 2, 2005

BASE BID

NO.	BID QUANTITY		DESCRIPTION	CITY ESTIMATE UNIT PRICE	CITY ESTIMATE TOTAL	1. HARDY & HARPER, INC. SANTA ANA UNIT PRICE	1. HARDY & HARPER, INC. SANTA ANA TOTAL	2. ALL AMERICAN ASPHALT CORONA UNIT PRICE	2. ALL AMERICAN ASPHALT CORONA TOTAL	3. COPP CONTRACTING, INC BUENA PARK UNIT PRICE	3. COPP CONTRACTING, INC BUENA PARK TOTAL	AVERAGE OF BIDS UNIT PRICE	AVERAGE OF BIDS TOTAL
1	1,800	TON	ASPHALT CONCRETE BASE COURSE	$130.00	$234,000.00	$125.00	$225,000.00	$130.00	$234,000.00	$153.00	$275,400.00	$136.00	$244,800.00
2	670	TON	AC SURFACE COURSE	$130.00	$87,100.00	$125.00	$83,750.00	$130.00	$87,100.00	$153.00	$102,510.00	$136.00	$91,120.00
3	70	TON	AC - SKIN PATCH (thickness: Varies)	$150.00	$10,500.00	$210.00	$14,700.00	$130.00	$9,100.00	$150.00	$10,500.00	$163.33	$11,433.33
4 (S)	1	LS	CRACK SEAL AND WEED KILLING OF STREETS TO BE SLURRIED PER BID ITEM NO. 5	$35,000.00	$35,000.00	$24,000.00	$24,000.00	$13,125.00	$13,125.00	$15,000.00	$15,000.00	$17,375.00	$17,375.00
5 (S)	1250	ELT	SLURRY SEAL TYPE II WITH 2% LATEX (1 E.T.L. = 2,000 LBS OF DRY AGGRAGATE)	$230.00	$289,800.00	$170.00	$214,200.00	$178.85	$225,351.00	$159.00	$200,340.00	$169.28	$213,297.00
6 (S)	42	ELT	SLURRY SEAL TYPE II (WITH 2% LATEX) (PARKING OF FIRE STATION # 4 AT 2300 PLACENTIA AVE - INCLUDING TRAFFIC CONTROL, MOBILIZATION, CRACK SEALING, WEED KILLING AND STRIPING - (1 E.T.L. = 2,000 LBS OF DRY AGGREGATE)	$330.00	$13,860.00	$390.00	$16,380.00	$272.00	$11,424.00	$275.00	$11,550.00	$312.33	$13,118.00
7 (S)	1	LS	CRACK SEAL AND WEED KILLING (NO SLURRY SEAL) - VICTORIA ST FROM HARBOR BLVD TO SANTA ANA RIVER BRIDGE	$32,000.00	$32,000.00	$18,000.00	$18,000.00	$17,430.00	$17,430.00	$20,000.00	$20,000.00	$18,476.67	$18,476.67
8 (S)	2	EA	ADJUST WATER VALVE CAN AND COVER TO FG	$450.00	$900.00	$1,000.00	$2,000.00	$525.00	$1,050.00	$500.00	$1,000.00	$675.00	$1,350.00
9 (S)	2	EA	ADJUST MANHOLE FRAME AND COVER TO FG	$450.00	$900.00	$500.00	$1,000.00	$525.00	$1,050.00	$1,200.00	$2,400.00	$741.67	$1,483.33
10 (S)	7	EA	TYPE I STOP LEGEND (12" LIMIT LINE)	$200.00	$1,400.00	$60.00	$420.00	$63.00	$441.00	$110.00	$770.00	$77.67	$543.67
11 (S)	19	EA	TYPE II STOP LEGEND - (WITH 50' DOUBLE YELLOW LINE)	$300.00	$5,700.00	$85.00	$1,615.00	$89.25	$1,695.75	$135.00	$2,565.00	$103.08	$1,958.58
12 (S)	4	EA	TYPE III STOP LEGEND - (WITH CROSS WALK AND 50' DOUBLE YELLOW LINE)	$400.00	$1,600.00	$185.00	$740.00	$194.25	$777.00	$220.00	$880.00	$199.75	$799.00
13 (S)	1160	LF	4" SKIP YELLOW LANE LINE (DETAIL 1)	$0.37	$429.20	$0.14	$162.40	$0.15	$174.00	$0.23	$266.80	$0.17	$291.07
14 (S)	3000	LF	4" SKIP YELLOW LANE LINE w/RPMs (DETAIL 2)	$0.50	$1,500.00	$0.19	$570.00	$0.20	$600.00	$0.23	$690.00	$0.21	$620.00
15 (S)	800	LF	4" SOLID YELLOW LANE LINE (DETAIL 24)	$0.37	$296.00	$0.16	$128.00	$0.17	$136.00	$0.23	$184.00	$0.19	$149.33
16 (S)	1190	LF	12" DOUBLE SOLID YELLOW WITH RPM's (DETAIL 22)	$0.40	$476.00	$0.55	$654.50	$0.58	$690.20	$0.30	$357.00	$0.48	$567.23
17 (S)	170	LF	6" SOLID WHITE LANE LINE WITH RPM's (Det 38)	$0.40	$68.00	$0.33	$56.10	$0.35	$59.50	$0.30	$51.00	$0.33	$55.53
18 (S)	530	SF	PAVEMENT MARKING ARROWS TYPE IV(L), IV (R), or VII PER CALTRANS STD. PLAN A24A - THERMOPLASTIC	$4.25	$2,252.50	$2.73	$1,446.90	$2.87	$1,521.10	$2.75	$1,457.50	$2.78	$1,475.17
19 (S)	1570	SF	MISC. PMT MARKING - THERMO	$5.70	$8,949.00	$3.72	$5,840.40	$3.90	$6,123.00	$3.50	$5,495.00	$3.71	$5,819.47
20 (S)	180	LF	4" SOLID WHITE STRIPING PAINT FOR PARKING STALL	$0.35	$63.00	$2.58	$464.40	$2.70	$486.00	$0.45	$81.00	$1.91	$343.80
21 (S)	4600	LF	6" WHITE BIKE LANE LINE (DETAIL 39)	$0.35	$1,610.00	$0.23	$1,058.00	$0.25	$1,150.00	$0.18	$828.00	$0.22	$1,012.00
22 (S)	900	LF	BIKE LANE (DROP LINE INTERSECTION LINE) (DETAIL 39A)	$0.35	$315.00	$0.23	$207.00	$0.25	$225.00	$0.18	$162.00	$0.22	$198.00
23 (S)	11	EA	"BIKE LANE" & MODIFIED TYPE I ARROW PAVEMENT MARKING IN PAINT	$60.00	$660.00	$77.50	$852.50	$81.50	$896.50	$45.00	$495.00	$68.00	$748.00
24 (S)	1900	LF	12" WIDE CROSSWALK OR LIMIT LINE THERMO IN WHITE	$2.00	$3,800.00	$1.50	$2,850.00	$1.58	$3,002.00	$1.65	$3,135.00	$1.58	$2,995.67
25 (S)	1060	LF	12" WIDE CROSSWALK OR LIMIT LINE THERMO IN YELLOW	$2.00	$2,120.00	$1.50	$1,590.00	$1.58	$1,674.80	$1.65	$1,749.00	$1.58	$1,671.27
26 (S)	13	EA	50 LF LONG - 4" SOLID WHITE LANE LINE WITH TYPE A & C RPMS PER DETAIL A	$30.00	$390.00	$30.79	$400.27	$29.85	$388.05	$27.00	$351.00	$29.21	$379.77
27 (S)	5200	LF	12" DOUBLE YELLOW WITH RPM's (DETAI 22)	$0.75	$3,900.00	$0.55	$2,860.00	$0.58	$3,016.00	$0.30	$1,560.00	$0.48	$2,478.67
28 (S)	1260	LF	12" DOUBLE YELLOW LANE LINE WITH RPM's (DETAIL 21 & 23)	$0.75	$945.00	$1.23	$1,549.80	$1.30	$1,638.00	$1.00	$1,260.00	$1.18	$1,482.60
29 (S)	1190	LF	8" SOLID WHITE LANE LINE (DETAIL 38A)	$0.60	$714.00	$0.23	$273.79	$0.25	$297.50	$0.26	$309.40	$0.25	$293.53
30 (S)	2630	LF	6" SOLID WHITE LANE LINE WITH RPM's (DETAIL 38)	$0.80	$2,104.00	$0.24	$631.20	$0.25	$657.50	$0.32	$841.60	$0.27	$710.10
31 (S)	11500	LF	4" skip WHITE LANE LINE WITH RPM's (DETAILS 8 & 10)	$0.65	$7,475.00	$0.40	$4,600.00	$0.42	$4,830.00	$0.53	$6,095.00	$0.45	$5,175.00
32 (S)	60	EA	TYPE "D" OR "E"REFLECTIVE RPM'S AS DIRECTED BY THE ENGINEER	$15.00	$900.00	$2.49	$149.40	$2.62	$157.20	$3.50	$210.00	$2.87	$172.20
33 (S)	250	LF	TWO-WAY LEFT TURN LANE (DET. 32)	$0.50	$125.00	$0.54	$135.00	$0.57	$142.50	$1.00	$250.00	$0.70	$175.83
34 (S)	90	EA	INSTALL REFLECTORIZED BLUE RAISED MARKER FOR FIRE HYDRANT	$15.00	$1,350.00	$5.00	$450.00	$5.25	$472.50	$3.50	$315.00	$4.58	$412.50
35	1	LS	PROJECT MANAGEMENT	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00	$18,000.00
					$771,291.70		$646,734.57		$648,881.10		$687,058.30		$669,891.32

ALTERNATE ITEM

NO.	BID QUANTITY		DESCRIPTION	CITY ESTIMATE UNIT PRICE	CITY ESTIMATE TOTAL	1. HARDY & HARPER, INC. SANTA ANA UNIT PRICE	1. HARDY & HARPER, INC. SANTA ANA TOTAL	2. ALL AMERICAN ASPHALT CORONA UNIT PRICE	2. ALL AMERICAN ASPHALT CORONA TOTAL	3. COPP CONTRACTING, INC BUENA PARK UNIT PRICE	3. COPP CONTRACTING, INC BUENA PARK TOTAL	AVERAGE OF ALTERNATE UNIT PRICE	AVERAGE OF ALTERNATE TOTAL
A	18,750	SY	CONSTRUCT CAPE SEAL	$0.00	$0.00	$4.40	$82,500.00	$4.33	$81,187.50	$3.04	$57,000.00	$3.92	$73,562.50
							$82,500.00		$81,187.50		$57,000.00		$73,562.50

ATTACHMENT 2