Quote

Farm Sports Complex Fields 5 & 6
Costa Mesa, California
Date: April 14, 2010
To: Bart Mejia

Equipment Description

Light-Structure Green™ System delivered to your site in Five Easy Pieces™

- (6) Pre-cast concrete bases
- (6) Galvanized steel poles
- UL Listed remote electrical component enclosure
- Pole length wire harness
- (24) Factory-aimed and assembled luminaires

Also Includes:

- Energy savings of more than 50% over a standard lighting system
- 50% less spill and glare light than Musco's prior industry leading technology
- Musco Constant 25™ warranty and maintenance program that eliminates 100% of your maintenance costs for 25 years, including labor and materials
- Guaranteed constant light level of 20 footcandles for 25 years, +/- 10% per IESNA RP-06-01
- Two group re-lamps at the end of the lamps' rated life, 5000 hours
- Reduced energy consumption
- Control Link® Control & Monitoring System for flexible control & solid management of your lighting system
- Lighting Contactors sized for site voltage and phasing
- Structural calculations per the CA 07 Building code by a CA State Licensed Structural Engineer
- Sales Tax is included
- Freight / Delivery are included. Please Note unloading of the equipment is NOT included and will be the responsibility of the City or Contractor. Musco will coordinate delivery dates with the accepting party.
- Field Aiming Services are included and will be provided by Musco Field technicians

Quotation Price

Musco's Light Structure Green™ Materials as described above and delivered to the job site:	**$ 80,000.00**
Sales Tax (8.75%):	**$ 7,000.00**
Total:	**$ 87,000.00**

Lead Time and Delivery Information:

Delivery to the job site from the time of order, submittal approval, and confirmation of order details including voltage and phase, pole locations is approximately 30-45 days. Due to the built-in custom light control per luminaire, pole locations need to be confirmed prior to production. Changes to pole locations after the product is sent to production could result in additional charges.

Notes

Quote is based on:

- Shipment of entire project together to one location
- Field size of 300' x 180' for Soccer Field #5
- Field size of 300' x 180' for Soccer Field #6
- Electrical system per site voltage and phase
- Structural code and wind speed = 2007 CBC, 85 MPH, Exposure C
- Confirmation of pole locations prior to production
- Musco Design #138485; dated November 10, 2008

Thank you for considering Musco for your sports lighting needs. Please contact me with any questions.

Karin Pekala
Musco Project Manager
Musco Sports Lighting, LLC
Phone: 858-755-2697
E-mail: karin.pekala@musco.com
Fax: 858-755-2698